

Scaffold Sheeting

PRODUCT	ROLL SIZE	MIL (THICKNESS) Wt. Per Meter Sq.	Approx. Wt. Per Roll	Approx. No. Eyelet Straps Per Roll	Approx. Man Hours Per Roll
Scaf-lite SL7-280	7' 4" x 136"	10 mil. 280 g/m ²	70 lbs.	2040 (+-) 1 Double Strap Top 3 Single Straps Spaced	*4 Hours Up & Down
Scaf-lite FR SL7-280 FR	7' 4" x 136"	10 mil. 280 g/m ²	70 lbs.	2040 (+-) 1 Double Strap Top 3 Single Straps Spaced	*4 Hours Up & Down
Scaf-lite 13' FR SL1300-250FR	13' x 100'	10 mil. 280 g/m ²	70 lbs.	1800 (+-) 1 Double Strap Top 4 Single Straps Spaced	*3 Hours Up & Down

BUNGEE - ELASTIC ROUND HEAD	733-382	Approx. 200 per 1000 sq. ft.
SREW-LOC CONNECTORS	733-360	Optional / Approx. 200 per 1000 sq. ft.
ZIPPER DOORWAY (54" x 72") Approx. Opening Size 40" x 52	733-630	Optional
SEALING TAPE - WHITE - 2" x 180'	733-616	Optional
- 4" x 180'	733-618	
- 6" x 180'	733-619	

* NOTE: These times are based on the averages of green and experienced crews for the staging, deployment, dismantling, and clean up of the sheeting applied to a straight run of scaffold, in our geographic location.

SCAF-LITE SCAFFOLD SHEETING STRAPING

On a roll of 7'4" wide there are 5 eyelet bands or straps – one is a double eyelet band and the other are single straps. The approximate centerline spacing of the eyelet strap to strap is as follows:

7'4" Wide

- 3"
- 5 ¼"
- 32 ½"
- 59"
- 85 ½"

On a roll of 13' wide there are 6 eyelet bands or straps – one is a double eyelet band and the other are single straps. The approximate centerline spacing of the eyelet strap to strap is as follows:

13' Wide

- 4"
- 6 ¾"
- 43"
- 80"
- 116 ¾"
- 153 ½"

To the best of our knowledge, these are typical property values & are intended as guides only, not as specification limits. Eagle Industries of Louisiana, Inc. makes no warranties as to the fitness for a specific use or merchantability of products referred to, no guarantee of satisfactory results from reliance upon contained information or recommendations, & disclaims all liability for resulting loss or damage.



TOLL FREE: 888.692.2490
www.eagleencl.com

Revised 05/2008

Scaffold Sheeting Tips

- SCAFFOLD SHEETING CAN BE INSTALLED HORIZONTALLY OR VERTICALLY
- HORIZONTAL INSTALLATIONS PROVIDE MAXIMUM PROTECTION AS A WATER SHED AND WIND DEFLECTOR
- APPROXIMATE POSSIBLE ATTACHMENT POINTS AVAILABLE PER ROLL
7'4" X 136' 2040 (+/-) 13' X 100' 1800 (+/-)
- BUNGEE TIES SHOULD BE SECURED **TIGHTLY** TO SCAFFOLD STRUCTURE
(Use **double or triple wrap if necessary**)
- BUNGEE TIES SHOULD BE ATTACHED AT EVERY POINT WHERE THE EYELET BAND INTERSECTS THE SCAFFOLD STRUCTURE INCLUDING CROSS BRACES, ETC.

***** **MINIMUM OF 1 1/2 BUNGEE TIES PER 10 sq/ft OF SHEETING below 30 ft.**

***** **MINIMUM OF 2 BUNGEE TIES PER 10 sq/ft OF SHEETING above 30 ft.**

- SCREW-LOC CONNECTORS OR BUNGEE TIE CAN BE USED TO JOIN MULTIPLE PANELS AT THE OVERLAP
- TAPING OVERLAP SEAMS IS RECOMMENDED FOR A COMPLETELY SEALED PROJECT (HEATING, NEGATIVE AIR PROJECTS, ETC.)
- USE OF ZIPPER DOORS IS RECOMMENDED FOR ACCESS TO THE WORK AREA.
- REPAIR ANY & ALL DAMAGES OR BREACHES ASAP.
- EVERY EFFORT MUST BE MADE TO COMPLETELY ENCLOSE SCAFFOLD WITH SHEETING AS NOT TO ALLOW WIND TO ENTER FROM THE TOP, BOTTOM, SIDES, OR BEHIND THE SCAFFOLD STRUCTURE.
- UNDER AVERAGE CONDITIONS IT IS SUGGESTED 150 – 200 BUNGEE TIES, AND 100 – 115 SCREW-LOC CONNECTORS PER 7'4" X 136' ROLL

To the best of our knowledge, these are typical property values & are intended as guides only, not as specification limits. Eagle Industries of Louisiana, Inc. makes no warranties as to the fitness for a specific use or merchantability of products referred to, no guarantee of satisfactory results from reliance upon contained information or recommendations, & disclaims all liability for resulting loss or damage.



TOLL FREE: 888.692.2490
www.eagleencl.com

Revised 05/2008